# Concrete pipe lifting sling

**Product information**



Six different concrete pipe lifting sling with 2- and 3-legs. P model slings are equipped with a standard jaw. In the I model slings, the jaw is wider than normal, and in the K model slings, the jaw is higher than normal and is suitable for concrete pipes equipped with rubber rings. In all models, the chain length is 1.5 m.

**Models**:

- **KRT2P**: 2-legs | chain leg 1,5 m | standard jaw P-model
- **KRT2I**: 2-legs | chain leg 1,5 m | wide jaw I-model
- **KRT2K**: 2-legs | chain leg 1,5 m | high jaw K-model | with a rubber sealing pipe clamps
- **KRT3P**: 3-legs | chain leg 1,5 m | standard jaw P-model
- **KRT3I**: 3-legs | chain leg 1,5 m | wide jaw I-model
- **KRT3K**: 3-legs | chain leg 1,5 m | high jaw K-model | with a rubber sealing pipe clamps

You can also order the jaws individually – you can find them here.

... *Read more*

**Material:** Steel
**Marking:** CE-mark
**Finish:** Painted, yellow
**Note:** L-dimension is height of jaw's grip area
**Warning:** Not to be heat-treated

**Safety factor:** 4:1

© November 2026 - All Rights Reserved

Forankra
Secures everything in transit™

# Concrete pipe lifting sling

## Blueprint




## Technical data

| Part code | Code | WLL ton | Jaw width mm | L mm | Weight kg |
|---|---|---|---|---|---|
| KRT2P | KRT2P | 2 | 60-120 | 245 | 25 |
| KRT2I | KRT2I | 2 | 80-170 | 235 | 35 |
| KRT2K | KRT2K | 2 | 60-120 | 345 | 35 |
| KRT3P | KRT3P | 3 | 60-120 | 245 | 37 |
| KRT3K | KRT3K | 3 | 60-120 | 345 | 45 |
| KRT3I | KRT3I | 3 | 80-170 | 235 | 46 |

© November 2026 - All Rights Reserved